

SPECIFICATION




■ Features :

- Universal AC input / Full range
- Built-in active PFC function, PF>0.94
- High efficiency up to 89%
- * Withstand 300VAC surge input for 5 seconds
- Protections: Short circuit / Overload / Over voltage / Over temperature
- * Built-in cooling fan ON-OFF control
- Built-in DC OK signal
- * Built-in remote ON-OFF control
- Standby 5V@0.3A
- Built-in remote sense function
- No load power consumption<0.75W (Note.7)
- Current sharing up to 2400W (3+1) (24V,36V,48V)
- 5 years warranty

Pc CBCE

MODEL		HRPG-600-3.3	HRPG-600-5	HRPG-600-7.5	HRPG-600-12	HRPG-600-15	HRPG-600-24	HRPG-600-36	HRPG-600-48	
	DC VOLTAGE	3.3V	5V	7.5V	12V	15V	24V	36V	48V	
	RATED CURRENT	120A	120A	80A	53A	43A	27A	17.5A	13A	
ОИТРИТ	CURRENT RANGE	0 ~ 120A	0 ~ 120A	0 ~ 80A	0 ~ 53A	0 ~ 43A	0 ~ 27A	0 ~ 17.5A	0 ~ 13A	
	RATED POWER	396W	600W	600W	636W	645W	648W	630W	624W	
	RIPPLE & NOISE (max.) Note.2	100mVp-p	100mVp-p	100mVp-p	120mVp-p	150mVp-p	150mVp-p	200mVp-p	240mVp-p	
	VOLTAGE ADJ. RANGE	2.8 ~ 3.8V	4.3 ~ 5.8V	6.8 ~ 9V	10.2 ~ 13.8V	13.5 ~ 18V	21.6 ~ 28.8V	28.8 ~ 39.6V	40.8 ~ 55.2V	
	VOLTAGE TOLERANCE Note.3	±2.0%	±2.0%	±2.0%	±1.0%	±1.0%	±1.0%	±1.0%	±1.0%	
	LINE REGULATION	±0.5%	±0.5%	±0.5%	±0.3%	±0.3%	±0.2%	±0.2%	±0.2%	
	LOAD REGULATION	±1.0%	±1.0%	±1.0%	±0.5%	±0.5%	±0.5%	±0.5%	±0.5%	
	SETUP, RISE TIME	1000ms, 50ms/230VAC 2500ms, 50ms/115VAC at full load								
	HOLD UP TIME (Typ.)	16ms/230VAC 16ms/115VAC at full load								
		85 ~ 264VAC	120 ~ 370VI							
	FREQUENCY RANGE	65~264VAC 120~370VDC 47~63Hz								
	POWER FACTOR (Typ.)	PF>0.94/230VA	1C PE>0.0	9/115VAC at full	load					
INPUT	EFFICIENCY (Typ.)	78.5%	82%	86%	88%	88%	88%	89%	89%	
INFOI	AC CURRENT (Typ.)	7.6A/115VAC	3.6A/230VA		00 /6	0070	0070	0376	0370	
	INRUSH CURRENT (Typ.)	35A/115VAC	70A/230VA							
	() ,			<i>-</i>						
	LEAKAGE CURRENT	<1.2mA/240VAC								
	OVERLOAD	105 ~ 135% rated output power								
				ent limiting, recov		1	1	44.4.40.01/	F7.0 07.0	
PROTECTION	OVER VOLTAGE	3.96 ~ 4.62V 6 ~ 7V 9.4 ~ 10.9V 14.4 ~ 16.8V 18.8 ~ 21.8V 30 ~ 34.8V 41.4 ~ 48.6V 57.6 ~ 67.2V								
		Protection type: Shut down o/p voltage, re-power on to recover								
	OVER TEMPERATURE	Shut down o/p voltage, recovers automatically after temperature goes down								
	5V STANDBY	5VSB: 5V@0.3A; tolerance ±5%, ripple: 50mVp-p(max.)								
FUNCTION	DC OK SIGNAL	PSU turn on: 3.3 ~ 5.6V; PSU turn off: 0 ~ 1V								
1011011011	REMOTE CONTROL	RC+ / RC-: 4 ~ 10V or open = power on; 0 ~ 0.8V or short = power off								
	FAN CONTROL (Typ.)	Load 35±15% or RTH2≧50°C Fan on								
	WORKING TEMP.	-40 ~ +70°C (Refer to "Derating Curve")								
	WORKING HUMIDITY	20 ~ 90% RH non-condensing								
ENVIRONMENT	STORAGE TEMP., HUMIDITY	-40 ~ +85°C, 10 ~ 95% RH								
	TEMP. COEFFICIENT	±0.03%/°C (0~50°C)								
	VIBRATION	10 ~ 500Hz, 5G 10min./1cycle, 60min. each along X, Y, Z axes								
	SAFETY STANDARDS	UL60950-1, TUV EN60950-1 approved								
SAFETY &	WITHSTAND VOLTAGE	I/P-O/P:3KVAC	I/P-FG:2KV/	AC O/P-FG:0.	5KVAC					
EMC	ISOLATION RESISTANCE	I/P-O/P, I/P-FG	, O/P-FG:100M	Ohms / 500VDC	C / 25°C / 70% RH	1				
(Note 4)	EMC EMISSION	Compliance to EN55022 (CISPR22) Class B, EN61000-3-2,-3								
	EMC IMMUNITY	Compliance to EN61000-4-2,3,4,5,6,8,11, EN55024, EN61000-6-2, heavy industry level, criteria A								
	MTBF	•					,,			
OTHERS	DIMENSION	147.7K hrs min. MIL-HDBK-217F (25°C) 218*105*63.5mm (L*W*H)								
O I I I I I I	PACKING	1.58Kg;8pcs/13	, ,							
NOTE	All parameters NOT special Ripple & noise are measure Tolerance: includes set up The power supply is consid a 360mm*360mm metal pla perform these EMC tests, p Derating may be needed ur Length of set up time is me	specially mentioned are measured at 230VAC input, rated load and 25°C of ambient temperature. leasured at 20MHz of bandwidth by using a 12" twisted pair-wire terminated with a 0.1uf & 47uf parallel capacitor. set up tolerance, line regulation and load regulation. considered a component which will be installed into a final equipment. All the EMC tests are been executed by mounting the unit on letal plate with 1mm of thickness. The final equipment must be re-confirmed that it still meets EMC directives. For guidance on how to lests, please refer to "EMI testing of component power supplies." (as available on http://www.meanwell.com) and under low input voltages. Please check the derating curve for more details. It is measured at first cold start. Turning ON/OFF the power supply may lead to increase of the set up time. Imption<0.75W when RC+ & RC- (CN100 pin3,4) 0 ~ 0.8V or short.								







Assignment

	-	
	Pin No.	Assignment
	1	AC/L
Г	2	AC/N
	3	FG ±

7 toolgilliont				
Pin No.	Assignment			
1~3	-V			
4~6	+V			

			,		
Pin No.	Assignment	Pin No.	Assignment	Mating Housing	Terminal
1	AUXG	6,8	GND		
2	AUX	7	DC-OK	UD0 DE44 40D0	UD0 DE44 **00
3	RC+	9	+S	HRS DF11-10DS or equivalent	or equivalent
4	RC-	10	-S	or oquivaloni	or oquivalent
5	CS				





■ Function Description of CN100

Pin No.	Function	Description
1	AUXG	Auxiliary voltage output ground. The signal return is isolated from the output terminals (+V & -V).
2	AUX	Auxiliary voltage output, 4.75~5.25V, referenced to pin 1(AUXG). The maximum load current is 0.3A. This output is not controlled by the "remote ON/OFF control".
3	RC+	Turns the output on and off by electrical or dry contact between pin 4 (RC-), Short: Power OFF, Open: Power ON.
4	RC-	Remote control ground.
5	cs	Current sharing signal. When units are connected in parallel, the CS pins of the units should be connected to allow current balance between units.
6,8	GND	This pin connects to the negative terminal(-V). Return for DC-OK signal output.
7	DC-OK	DC-OK signal is a TTL level signal, referenced to pin8(DC-OK GND). High when PSU turns on.
9		Positive sensing. The +S signal should be connected to the positive terminal of the load. The +S and -S leads should be twisted in pair to minimize noise pick-up effect. The maximum line drop compensation is 0.5V.
10		Negative sensing. The -S signal should be connected to the negative terminal of the load. The -S and +S leads should be twisted in pair to minimize noise pick-up effect. The maximum line drop compensation is 0.5V.

■ Function Manual

1.Remote Sense

The remote sensing compensates voltage drop on the load wiring up to 0.5 V.





Fig 1.1

2.DC-OK Signal

 $\ensuremath{\mathsf{DC}\text{-}\mathsf{OK}}$ signal is a TTL level signal. High when PSU turns on.

Between DC-OK(pin7) and GND(pin6,8)	Output Status
3.3 ~ 5.6V	ON
0 ~ 1V	OFF



CN100 AUX AUXG 1 RC+ RC-GND CS GND DC-OK 10 -S +S 9

Fig 2.1




3.Remote Control

The PSU can be turned ON/OFF by using the

"Remote	Control"	function.
IXCIIIOLO	OUILLIOI	Tullotion.

Between RC+(pin3) and RC-(pin4)	Output Status
SW ON (Short)	OFF
SW OFF (Open)	ON







Fig 3.1

4. Current Sharing with Remote Sensing (Only for 24V, 36V and 48V)

HRPG-600 has the built-in active current sharing function and can be connected in parallel to provide higher output power:

- (1)Parallel operation is available by connecting the units shown as below.
 - (+S,-S,CS and GND are connected mutually in parallel).
- (2) Difference of output voltages among parallel units should be less than 2%.
- (3) The total output current must not exceed the value determined by the following equation.
 - (output current at parallel operation)=(Rated current per unit)×(Number of unit)×0.9
- (4)In parallel operation 4 units is the maximum, please consult the manufacturer for applications of more connecting in parallel.
- (5) The power supplies should be paralleled using short and large diameter wiring and then connected to the load.



Note: 1.In parallel connection, maybe only one unit (master) operate if the total output load is less than 2% of rated load condition.

The other PSU (slave) may go into standby mode and its output LED and relay will not turn on.

2.2% min. of dummy load is required.